

Overview

What is this standard about?

This standard covers the need to confirm installation instructions before commencing a job. All the requirements of the work have to be confirmed and all relevant specifications will have to be obtained.

The type of access equipment used during the work has to be agreed and its availability confirmed. Every detail relevant to the commencement and completion of the work has to be obtained. All information has to be recorded accurately and all relevant documents completed.

Who is this standard for?

This standard is for you if you install roofline products, e.g. fascias, soffits and bargeboards

Confirm installation instructions

Performance criteria

- You must be able to:*
1. comply with health and safety requirements, and relevant statutory regulations and industry standards/codes of practice fully at all times
 2. obtain installation instructions in a timely manner that are clear and accurate from the appropriate people in the organisation, including the schedule and location of the installation
 3. obtain all important specifications for the installation promptly
 4. confirm that all relevant permits to work have been obtained promptly
 5. agree the access equipment needed to work safely and efficiently and confirm its availability
 6. identify what equipment and materials will be required to complete the installation work to comply with all relevant legislation
 7. agree with colleagues in a clear and cohesive manner how the installation work will be completed
 8. record information on the specifications and the installation work needed to deliver them accurately and in the appropriate information systems

Confirm installation instructions

Knowledge and understanding

- You need to know and understand:*
1. the relevant health and safety requirements, and relevant statutory regulations and industry standards/codes of practice that have to be complied with
 2. who is authorised to provide installation instructions
 3. how to obtain and confirm the specifications of the installation
 4. what permits to work are required for different types of installations
 5. what type of access equipment should be used for different types of installation and who is competent to erect these
 6. what type of problems could occur with the installation and the standard operating procedures for dealing with them
 7. what type of environmental problems could occur with the installation and the standard operating procedures for dealing with them
 8. the correct equipment and materials for the different types of installation
 9. what information systems should be used and why it is important to record information

Scope/range**Access equipment**

- 1 boards
- 2 hop-ups
- 3 ladders
- 4 props
- 5 scaffolding
- 6 specialist access equipment
- 7 trestles
- 8 working platforms

Equipment

- 1 battery-powered equipment
- 2 machinery
- 3 mains-powered equipment
- 4 manual tools

Health and safety requirements

- 1 identification of hazards
- 2 use of personal protective equipment
- 3 use of safety equipment

Information systems

- 1 electronic
- 2 manual

Installation

- 1 bargeboards
- 2 fascias
- 3 rainwater systems
- 4 soffits

Installation work

- 1 accessing the roof
- 2 cutting
- 3 fixing

Confirm installation instructions

4 handling and transporting materials

Materials

- 1 consumables
- 2 felt
- 3 fixings
- 4 pipes
- 5 rafter feet
- 6 tiles

Problems

- 1 organisational
- 2 resources
- 3 technical

Specifications

- 1 dimensions
- 2 materials
- 3 planning requirements
- 4 position

Environmental problems

- 1 rain
- 2 cold
- 3 heat
- 4 high winds

Confirm installation instructions

Developed by Proskills

Version Number 2

Date Approved November 2012

Indicative Review Date April 2017

Validity Current

Status Original

Originating Organisation Proskills

Original URN PROFBS3

Relevant Occupations Construction Operatives

Suite Installation of Domestic Fascias, Soffits and Bargeboards

Keywords Fascias, Soffits and Bargeboards
